

FAP Overview (EWR): Checklists, Site Evaluation, Training, Documentation, Installed System Inspection and Performance.

Presented to: Chinese Delegation Participants
By: Carmen Tedeschi FAA, , AJP-652
Date: October 19th, 2010



Federal Aviation
Administration



Presentation Overview

- **Checklists**
 - Part of FAP, includes detail breakout (Inspection...)
- **Site Survey – Pre-Construction Evaluation**
 - Map and Paper Study, and Field Data Collection
- **Training AND Testing**
 - Training Requirement for certified Operators/Maintainers
- **Documentation**
 - Commercial Instruction Book (CIB)
 - Field Reference Data File (FRDF)
- **Installed System Inspection**
- **Installed System Performance**
 - Verification of as-advertised user-level performance.



GBAS CAT I Approval Overview

- **Scope of this Presentation**





Site Survey – Pre- Construction Evaluation

- Utilize the Siting Documentation, and ALP (Map and Paper) to aid in choosing appropriate sites for evaluation. GPS and VDB performance considered.




Site Survey Continued – Identify Several Sites and perform GPS data collection, and VDB Line Of Site (LOS) study.

GPS Sky Plots Site C



GPS Sky Plots Site B



Training AND Testing Requirement for certified Operators/Maintainers



Course Completion Certificate
This certificate affirms that:

has successfully completed the course entitled:
SLS-4000 GBAS Maintenance Training

And is Factory Approved to Operate and Maintain the
HG4031 GBAS Ground Facility

Course Completed: May 11 to May 15, 2009

Mark Cady - Instructor
Honeywell Aerospace

Patrick Shannon - Instructor
Honeywell Aerospace

Brian Koosmann – Technical Manager
Honeywell Aerospace

4. Identify Facility Reference Documents (Set-Up Values) and Validate Equipment Configuration			X	X	X
a. Facility Operating Files	3-7.12		X		✓
b. Enabled Approaches	3-7.7		X		✓
c. Facility Operating Parameters Reference Data		Local Document	X		✓
d. Facility Wiring Reference Data		Local Document	X		✓

AIRWAY FACILITIES MAINTENANCE PERSONNEL CERTIFICATION PROGRAM

FMIS # 89836001

1) GBAS TYPE HONEYWELL SLS-4000 (NP136)

ESTIMATED TIME: 3 Hours

REVISION DATE:

REASON FOR REPLACEMENT TO REPLACE: New Exam (05/29/09)

FORWARD RECOMMENDED CHANGES/CORRECTIONS TO:

FAA NATIONAL HEADQUARTERS
 Air Traffic Organization, Workforce Development
 Technical Operations Training Division
 800 Independence Avenue, SW
 Washington, D. C. 20591
 Telephone: [202] 267-8280

•In addition to vendor maintainer course completion, the FAA also tests trained maintainers.



Commercial Instruction Book (CIB) – Site Neutral

Honeywell

Honeywell International Inc.
Aerospace Minneapolis
2500 Ridgway Parkway
Minneapolis, Minnesota 55413
U.S.A.
CAGE: 94680

Satellite Landing System


Ground Based Augmentation System

Model SLS-4000
Part Number YG4031EA01

(Includes GBAS Ground Facility
Part Number HG4031EA01)

Ground Equipment Manual

- Content and Format verified as part of SDA.
- Facility Approval Item – Documentation Only



Required Approval Steps and Documents:

- **Checklists and associated field Inspection/Measurements:**
 - System (extensive and includes SLS-4000 Rack, CIB, etc.)
 - Shelter
 - RSMUs
 - VDB Antenna
 - Battery Rack
 - MDT/ATSU
- **Field Reference Data File (FRDF):**
 - Physical/Local site specific data, artifacts, FCC, and backup software.
- **Site Acceptance Test Report Content (Summary):**
 - MSD, Adaptation Data, FAS data, DCP software, Survey
 - 14-day Test
 - Formal Flight Inspection Report
 - Summarizes the above and provides sign-off by Installer, Non-Fed Coordinator, and Service Provider.

FRDF Checklist, and FRDF Site Specifics

The table shows the items that are required to be resident in the Field Reference Facility Data File (FRDF) for the EWR GBAS (SLS-4000). The **Site Inspection conducted @ EWR on 12/30/09** (This is the third revision) is reflected here. See also Site Acceptance Checklists and Site Acceptance Checklist (Summary).

Field Reference Data File - Content			
Item	Data Content	Comment	Status
Facility Locations:	Country, City, State, Province, etc. of facility	None	OK
GBAS	Latitude, Longitude, Altitude of facility	None	OK
Air Traffic Control	Location and contact information	None	OK
Maintenance Control	Location of the Maintenance Control Facility when remote maintenance is initiated	None	OK
ANSP or Owner	Address of the applicable ANSP or owner of the system and contact information	None	OK
Honeywell Repair Center	Address of and contact information	None	OK
Equipment:			
Serial numbers	List of GBAS equipment serial numbers	None	OK
Operating frequency and time slot allocation	Identification of transmit license parameters	None	OK
Operating RF output power level	Identification of authorized RF output power levels	None	OK
AC input power specification	AC input power specified values	None	OK
AC input power as measured	AC input power as measured values	None	OK
VDB Transmission line signal loss	Measured signal loss	None	OK
Transmission line VSWR	Measured VSWR	None	OK
Loaded Binary CRC values	Identified Binary File CRC's	None	OK
Earth resistance measurements	Measured resistance to Earth for equipment and lightning ground	All Segments (Shelter, Signal, VDB, RSMUs, etc.)	OK
Site acceptance documents	All site testing results completed as part of system acceptance	FAA I FAATC in process.	In Work
RSMU surveyed positions	X-Y-Z coordinates of the installed RSMU's	None	OK
VDB Antenna surveyed	Latitude, longitude, altitude of	None	OK

FIELD COPY

NEWARK (KEWR)

FACILITY REFERENCE DATA FILE

Scott
1638 Fish Cove
Telephone: 609-882-2400 Fax: 609-882-5600
GROUND RESISTANCE TEST REPORT

Customer: *Sea El Electric Inc* Date: *12/30/09* Page: *1* of *2*
Customer Address: *1916 Morris Blvd To Williams NJ 07205* Project Number: *503-1672-2*
Owner: *Newark Airport* Last Inspection Report: *Acceptance*
Owner Address: *Various Locations* Last Inspection Date: *Acceptance*
Equipment Location: *G-BA3 Area* Air Temperature: *70°F*
Owner Identification: *G-BA3 Area* Relative Humidity: *50%*

Test Date	Location (PLCI)	Class	Distance (ft) to P2
	<i>G-BA3 VDB Antenna</i>	<i>20.2</i>	<i>100'</i>
		<i>0.33</i>	<i>90'</i>
		<i>0.28</i>	<i>80'</i>
		<i>0.26</i>	<i>70'</i>
		<i>0.25</i>	<i>60'</i>
		<i>0.23</i>	<i>50'</i>
		<i>0.25</i>	<i>40'</i>
		<i>0.25</i>	<i>30'</i>

REMARKS: *Results Acceptable*

Test Method: *3 Point Test*
Distance (ft) to C2: *100 Feet*

FIELD COPY

KEWR RSMU Positions 12-14-2009

MEASURED BY HONEYWELL
USING Trimble Survey Equipment
and EWR PAC

Near RSMU #1.

EWB_7
lat = 40w41'25.97608"N lon = 74w09'52.39269"W ellips hght=-30.522
x = 1321547.698
y = -4859246.502
z = 4136407.080

EWB_8K1
lat = 40w41'26.62964"N lon = 74w09'51.11102"W ellips hght=-26.634
x = 1321571.867
y = -4859228.482
z = 4136424.901

EWB_8K2
lat = 40w41'29.39715"N lon = 74w09'48.70871"W ellips hght=-26.061
x = 1321613.060
y = -4859159.917
z = 4136490.008

EWB_8K4
lat = 40w41'31.51600"N lon = 74w09'45.02887"W ellips hght=-26.227
x = 1321662.563
y = -4859017.871
z = 4136431.006

FRDF Checklist, and FRDF Site Specifics Continued

License to transmit	Official authorization to transmit from the regulatory authority. Normally, this document is posted in clear view with the shelter	None	OK
Security Issues:			
Local Security Procedures	Local procedures to be followed in case of a security issue, such as a shelter intrusion or other unauthorized access.	None	OK

Wireless Telecommunications Bureau
RADIO STATION AUTHORIZATION
DEPARTMENT OF TRANSPORTATION
FEDERAL AVIATION ADMINISTRATION
NEWARK LIBERTY INTERNATIONAL AIRPORT
NEWARK, NJ 07102
Station Number (FRN): 0003462488

EWR OMM Last updated: 1/26/2010 3:03 PM

	<u>Page No.</u>
Part I. OPERATIONAL REQUIREMENTS	
1. Licensing	4
a. Facility	4
b. Maintenance Technician	4
2. Notice to Airmen	4
3. Monitoring	5

STATION TECHNICAL SPECIFICATIONS

Fixed Location Address or Mobile Area of Operation
Loc. 1 Address: 0 km N of FAA Bldg 304, Newark Liberty Intl Airport
City: Newark County: ESSEX State: NJ
Lat (NAD83): 40-41-26.0 N Long (NAD83): 074-09-45.0 W ASR No.: 1271168 Ground Elev.: 3.0
No. of units:

Antennas
Loc. Ant. Frequencies
No. No. (MHz)
1 1 000114.52500000

Control Points
Control Pt. No. 1
Address: 2 Gateway Center, 16SW
City: Newark County: ESSEX

Ground Equipment Manual (GEM) Honeywell Doc 10165326-101	Provides approved operation and maintenance procedures for the system	None	OK
Operation and Maintenance Manual (OMM)	Provides site specific procedures and general procedures for the operation and maintenance of the system	None	OK
Record of calibration for site support equipment	Lists last calibrated dates and dates due for future calibration	<u>HLI to provide</u>	<u>In Work</u>
Site drawings	If available, provides maintenance data for commercial items	None	OK



Installed GBAS System Inspection

(This activity can go through several cycles before completion)

•Primary Areas For inspection:

•Shelter and Infrastructure

- HVAC. Power, Grounding, Lighting, etc.

•Indoor GBAS Equipment

- Equipment Rack/Tower (CPUs, VDB, etc.)

- Battery Rack

•Outdoor GBAS Equipment and Lightning Protections

- RSMU (Remote Satellite Measuring Unit)

 - Enclosure and Connections




 - RRA (Reference Receiver Antennas)

- VDBA (VHF Data Broadcast Antenna)

Installed System Inspection Shelter/General

This table is presented to document the results of the EWR SLS-4000 GBAS Site Inspection conducted @ EWR on 12/30/09 (this is the 3rd revision). The level of detail contained here will reflect any discrepancies determined during inspection. See also FRDF, and Site Acceptance Checklist (Summary).

System Installation Checklist – General/Shelter

#	Item	Requirement/Criteria	Results/ OK/Fail/TBF (To Be Finalized) In Work	Initials	Comments and/or Actions (HI, PA, PACMD, FAA/TC)
1	Test Equipment	Calibration stickers - calibration is current	OK	CT/CK	N/A
2	Bandpass Filter	Tuned to the licensed output frequency			
3	Adaptation Data File	Loaded into GBAS			
4	GBAS DCP software	Loaded into GBAS			
5					
6		<p>ata has ta ell, and d Site een</p>	In Work/TBF		

Installed System Inspection RSMU

RSMU Installation Checklist

#	Item	Requirement/Criteria	Results/ OK/Fail/TBF (To Be Finalized) or In Work	Initials	Comments
24	GPS Antennas	Surveyed position is known. Refer to paragraph 9-7.4 for specific requirements	OK	CT/JCK	None
25	GPS Antennas	GPS antennas are plumb to 0.5°	OK	CT/JCK	None
26	Time mark signals	Time mark output pulses from each of the installed RSMU's at the Surge Panel are present. See Figure 6-4 for wire assignments	OK	CT/JCK	
27	RSMU separation	>100 m to <300 m (reference GBAS Doc. 68001984)			
28	RSMU connection	Verify cables are connected properly and secure to RSMU			
29	Wiring	Correct wiring at Surge Panel per Figure 6-4			
30	RSMU obstructions	Verify no obstructions are penetrating the RSMU (reference GBAS Doc. 68001984)			



Installed System Inspection VDBA

VDB Antenna Installation Checklist

#	Item	Requirement/Criteria	Results/ OK/Fail/TBF (To Be Finalized) or In Work	Initials	Comments
38	Surveyed position	VDB antenna surveyed position is known and recorded in the Maintenance Log	OK	CT/CK	Lat/Lon and AGL on FCC License to TX on wall, and in FRDF. Lat/Lon in as-planned
39	Mounting	Mounting bolts/nuts are secure	OK		
40	Position	Line of sight exists to all supported runway ends	OK		
41	Transmission line	Length is within specifications for cable type used	OK		
42	Feed line connector weatherproof material	Ens mat con tran line			
43	Lightning protection	Ver gro ohn			
44	Rigidity	VDB sec			
45	Obstruction lights	Pre ope		CT/CK	None





EWR Installed System Performance Verification (in advance of Flight Inspection – Approval Requirement)

- Ground Based Performance Monitor System (GBPM) can be employed.



EWR GBPM Performance Data Plots



Questions or Comments

- **Carmen Tedeschi**
FAA WJH Technical Center
AJP-652 Navigation Team
carmen.tedeschi@faa.gov
609-485-7165

